

TEST REPORT

Test Order/Report No: BVIPL: CHEQUERED TILE/25951C/2240/1/2022
Job ID No: 2022/Jan/2134299-(UIN-22003509)

Date of Issue: 05-02-2022
Date of Receipt: 25-01-2022
Page 1 of 1

Issued to: Indo Enviro Integrated Solutions Limited
(Formerly IL and FS Environment Infrastructure and Services Limited) MCD Cand D
Waste Processing Plant, Gate No. 1, Hanuman Mandir Road,
Block No.31, Jahangirpuri, New Delhi-110033

TEST REPORT ON CHEQUERED TILE

Source of Sample# : Indo Enviro Integrated Solutions Limited
No. of Sample Tested : 1 (One)
Customer Reference# : Work Order No.21220200100148/21220200400137 Dated 21.01.2022
Project# : Not Furnished
Condition of Sample : Satisfactory (3 Nos.)
Sample Drawn by : Customer
Sample Identification# : Size 300*300*30mm
Grade/Type# : M-30
Brand# : Not Furnished
Period of Test : 27.01.2022 to 29.01.2022

Mechanical Testing-(Buildings Materials)-Chequered Tile

S. No.	Tests	Results	Requirement As Per IS: 13801-2013	Test Method
1.	Wet Transverse Strength, N/mm ²			
	1	3.9	3.0 Min.	IS: 13801 -2013
	2	3.9		
	3	4.4		
	Average	4.1		

As furnished by customer.

- Note: 1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with the disclaimer given at rear side of this report.
4. Any corrections invalidates this report.

For **BUREAU VERITAS (INDIA) PRIVATE LIMITED**
Construction Services Laboratory-Noida



BIPIN B NAYAK

Bipin B Nayak
Authorized Signatory
(Mechanical)



TEST REPORT

Test Order/Report No: BVIPL: PAVER BLOCKS/25951C/2240/1/2022
Job ID No: 2022/Jan/2134299-(UIN-22003506)

ULR - TC562422000001367F
Date of Issue: 09-02-2022
Date of Receipt: 25-01-2022
Page 1 of 1

Issued to: Indo Enviro Integrated Solutions Limited
(Formerly IL and FS Environment Infrastructure and Services Limited) MCD Cand D
Waste Processing Plant, Gate No. 1, Hanuman Mandir Road,
Block No.31, Jahangirpuri, New Delhi-110033

TEST REPORT ON PAVER BLOCKS

Source of Sample# : Indo Enviro Integrated Solutions Limited
No. of Sample Tested : 1 (One)
Customer Reference# : Work Order No.21220200100148/21220200400137 Dated 21.01.2022
Project# : Not Furnished
Condition of Sample : Satisfactory (8 Nos.)
Sample Drawn by : Customer
Sample Identification# : Paver Block, Size 300*150*60mm, Brick Tile
Grade/Type# : M-30
Brand# : Not Furnished
Period of Test : 26.01.2022 to 27.01.2022

Mechanical Testing-(Buildings Materials)-Paver Block

S. No.	Tests	Results	Requirement As per IS: 15658-2021	Test Method
1.	Compressive Strength, N/mm ²			
	1	60.6		
	2	58.4		
	3	54.7		
	4	60.9		
	5	59.4		
	6	52.6		
	7	60.1		
	8	58.4		
	Average	58.1	34.1 Min.	
	Individual Minimum	52.6	27.0 Min.	

As furnished by customer.

- Note: 1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with the disclaimer given at rear side of this report.
4. Any corrections invalidates this report.

For **BUREAU VERITAS (INDIA) PRIVATE LIMITED**
Construction Services Laboratory-Noida



BIPIN B NAYAK

Bipin
Authorized Signatory
(Mechanical)



Bureau Veritas (India) Private Limited
Construction Services Laboratory
A-8, Sector 6, Opp. Rohan Motors
Noida - 201 301, Uttar Pradesh
INDIA

Tel.: +91 120 4770050
lab.delhi@bureauveritas.com
www.bureauveritas.co.in
CIN: U74210MH2001PTC134262

Regd. Office:
72 Business Park, Ground Floor
Marol Industrial Area, MIDC
Cross Road 'C', Andheri (East)
Mumbai - 400 093. INDIA



TEST REPORT

Test Order/Report No: BVIPL: PAVER BLOCKS/25951C/2240/1/2022
Job ID No: 2022/Jan/2134299-(UIN-22003507)

ULR - TC562422000001368F
Date of Issue: 09-02-2022
Date of Receipt: 25-01-2022
Page 1 of 1

Issued to: Indo Enviro Integrated Solutions Limited
(Formerly IL and FS Environment Infrastructure and Services Limited) MCD Cand D
Waste Processing Plant, Gate No. 1, Hanuman Mandir Road,
Block No.31, Jahangirpuri, New Delhi-110033

TEST REPORT ON PAVER BLOCKS

Source of Sample# : Indo Enviro Integrated Solutions Limited
No. of Sample Tested : 1 (One)
Customer Reference# : Work Order No.21220200100148/21220200400137 Dated 21.01.2022
Project# : Not Furnished
Condition of Sample : Satisfactory (8 Nos.)
Sample Drawn by : Customer
Sample Identification# : Paver Block, Size 60mm, Milano SHape
Grade/Type# : M-30
Brand# : Not Furnished
Period of Test : 28.01.2022 to 29.01.2022

Mechanical Testing-(Buildings Materials)-Paver Block

S. No.	Tests	Results	Requirement As per IS: 15658-2021	Test Method
1.	Compressive Strength, N/mm ²			
	1	37.8		
	2	45.5		
	3	48.7		
	4	46.3		
	5	44.7		
	6	47.2		
	7	44.7		
	8	47.9		
	Average	45.4	34.1 Min.	
	Individual Minimum	37.8	27.0 Min.	

As furnished by customer.

- Note: 1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with the disclaimer given at rear side of this report.
4. Any corrections invalidates this report.

For **BUREAU VERITAS (INDIA) PRIVATE LIMITED**
Construction Services Laboratory-Noida



BIPIN B NAYAK

Bipin
Authorized Signatory
(Mechanical)



Bureau Veritas (India) Private Limited
Construction Services Laboratory
A-8, Sector 6, Opp. Rohan Motors
Noida - 201 301, Uttar Pradesh
INDIA

Tel.: +91 120 4770050
lab.delhi@bureauveritas.com
www.bureauveritas.co.in
CIN: U74210MH2001PTC134262

Regd. Office:
72 Business Park, Ground Floor
Marol Industrial Area, MIDC
Cross Road 'C', Andheri (East)
Mumbai - 400 093. INDIA

TEST REPORT

Test Order/Report No: BVIPL: PAVER BLOCKS/25951C/2240/1/2022
Job ID No: 2022/Jan/2134299-(UIN-22003508)

ULR - TC562422000001369F
Date of Issue: 09-02-2022
Date of Receipt: 25-01-2022
Page 1 of 1

Issued to: Indo Enviro Integrated Solutions Limited
(Formerly IL and FS Environment Infrastructure and Services Limited) MCD Cand D
Waste Processing Plant, Gate No. 1, Hanuman Mandir Road,
Block No.31, Jahangirpuri, New Delhi-110033

TEST REPORT ON PAVER BLOCKS

Source of Sample# : Indo Enviro Integrated Solutions Limited
No. of Sample Tested : 1 (One)
Customer Reference# : Work Order No.21220200100148/21220200400137 Dated 21.01.2022
Project# : Not Furnished
Condition of Sample : Satisfactory (8 Nos.)
Sample Drawn by : Customer
Sample Identification# : Paver Block, Size 200*165*60mm, Dumble Shape
Grade/Type# : M-30
Brand# : Not Furnished
Period of Test : 27.01.2022 to 28.01.2022

Mechanical Testing-(Buildings Materials)-Paver Block

S. No.	Tests	Results	Requirement As Eer IS: 15658-2021	Test Method
1.	Compressive Strength, N/mm ²			
	1	55.7		
	2	61.3		
	3	61.0		
	4	62.3		
	5	60.3		
	6	66.8		
	7	61.4		
	8	55.2		
	Average	60.5	34.1 Min.	
	Individual Minimum	55.2	27.0 Min.	

As furnished by customer.

- Note: 1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with the disclaimer given at rear side of this report.
4. Any corrections invalidates this report.

For **BUREAU VERITAS (INDIA) PRIVATE LIMITED**
Construction Services Laboratory-Noida



BIPIN B NAYAK
Bipin
Authorized Signatory
(Mechanical)





TEST REPORT

Test Order/Report No: BVIPL: PAVER BLOCKS/25951C/2240/1/2022
Job ID No: 2022/Jan/2134299-(UIN-22003510)

ULR - TC562422000001370F

Date of Issue: 09-02-2022

Date of Receipt: 25-01-2022

Page 1 of 1

Issued to: **Indo Enviro Integrated Solutions Limited**

(Formerly IL and FS Environment Infrastructure and Services Limited) MCD Cand D
Waste Processing Plant, Gate No. 1, Hanuman Mandir Road,
Block No.31, Jahangirpuri, New Delhi-110033

TEST REPORT ON PAVER BLOCKS

Source of Sample# : Indo Enviro Integrated Solutions Limited
No. of Sample Tested : 1 (One)
Customer Reference# : Work Order No.21220200100148/21220200400137 Dated 21.01.2022
Project# : Not Furnished
Condition of Sample : Satisfactory (8 Nos.)
Sample Drawn by : Customer
Sample Identification# : Paver Block, Size 300*300*60mm, Tech Tile
Grade/Type# : M-30
Brand# : Not Furnished
Period of Test : 28.01.2022 to 29.01.2022

Mechanical Testing-(Buildings Materials)-Paver Block

S. No.	Tests	Results	Requirement As per IS: 15658-2021	Test Method
1.	Compressive Strength, N/mm ²			
	1	37.8		
	2	40.3		
	3	39.8		
	4	41.7		
	5	43.3		
	6	47.7		
	7	41.6		
	8	40.8		
	Average	41.7	34.1 Min.	
	Individual Minimum	37.8	27.0 Min.	

As furnished by customer.

- Note: 1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with the disclaimer given at rear side of this report.
4. Any corrections invalidates this report.

For **BUREAU VERITAS (INDIA) PRIVATE LIMITED**
Construction Services Laboratory-Noida



BIPIN B NAYAK

Bipin
Authorized Signatory
(Mechanical)



Bureau Veritas (India) Private Limited
Construction Services Laboratory
A-8, Sector 6, Opp. Rohan Motors
Noida - 201 301, Uttar Pradesh
INDIA

Tel.: +91 120 4770050
lab.delhi@bureauveritas.com
www.bureauveritas.co.in
CIN: U74210MH2001PTC134262

Regd. Office:
72 Business Park, Ground Floor
Marol Industrial Area, MIDC
Cross Road 'C', Andheri (East)
Mumbai - 400 093. INDIA

Test Order/Report No: BVIPL: KERB STONE/25951C/2240/1/2022
Job ID No: 2022/Jan/2134299-(UIN-22003505)

Date of Issue: 05-02-2022
Date of Receipt: 25-01-2022
Page 1 of 1

Issued to: Indo Enviro Integrated Solutions Limited
(Formerly IL and FS Environment Infrastructure and Services Limited) MCD Cand D
Waste Processing Plant, Gate No. 1, Hanuman Mandir Road,
Block No.31, Jahangirpuri, New Delhi-110033

TEST REPORT ON KERB STONE

Source of Sample# : Indo Enviro Integrated Solutions Limited
No. of Sample Tested : 1 (One)
Customer Reference# : Work Order No.21220200100148/21220200400137 Dated 21.01.2022
Project# : Not Furnished
Condition of Sample : Satisfactory (5 Nos.)
Sample Drawn by : Customer
Sample Identification# : Size 300*300*150mm
Grade/Type# : M-25
Brand# : Not Furnished
Period of Test : 01.02.2022 to 04.02.2022

Mechanical Testing-(Buildings Materials)-Kerb Stone

S. No.	Weight, Kg	Length, mm	Diameter, mm	Crushing Load, kN	Compressive Strength, N/mm ²	Corrected Compressive Strength, N/mm ² (CCS*H/D)	Equivalent Cube Strength, N/mm ² (CCS *1.25)	Requirement As Per IS: 5758-2020	Test Method
1	2.453	145.08	100.29	233.4	28.3	26.6	33.3	30 Min.	IS:5758-2020 & IS: 516-(Part-IV)-2018
2	2.347	139.13	100.34	186.5	23.6	21.9	27.4		
3	2.484	144.59	100.39	204.1	25.8	24.3	30.4		
Average							30.4		

As furnished by customer.

- Note: 1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with the disclaimer given at rear side of this report.
4. Any corrections invalidates this report.

For BUREAU VERITAS (INDIA) PRIVATE LIMITED
Construction Services Laboratory-Noida



BIPIN B NAYAK

Bipin B Nayak
Authorized Signatory
(Mechanical)

